

BRUHATH BANGALORE MAHANAGARA PALIKE ,DASRAHALLI ZONE

Office Of The Executive Engineer, Project Division

SCHEDULE-B

NAME OF THE WORK: Construction Of Retaining Wall And other Development Works to Proposed Play ground
Mallasandra In ward No 13

SI No	Description Of Work	Unit	Qty	Rate To Be Quoted	
				In Figures (Rs)	In Words (Rs)
1	2	3	4	5	6
1	KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 1.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications.	Cum	389.07	178.85	One Hundred Seventy Eight Rupees and Eighty Four Paise Only
2	KSRB 4-1.2 : Providing and laying in position plain cement concrete of cum mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications.Specification No. KBS 4.1, 4.2	Cum	320.08	5236.92	Five Thousand Two Hundred Thirty Six Rupees and Ninety Two Paise Only
3	KSRB 4.2.2 : Providing and laying in position reinforced cement cum concrete of Design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @ 0.460 cum, with super plasticisers @ 3 liters conforming to IS 9103-1999 reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation for footings, pedestals, retaining walls, return walls, walls (any thickness) including attached pilasters, columnspillars, posts, struts, buttresses, bed blocks, anchor blocks & plinths etc., including cost of all materials, labour, HOM of machinery, curing, complete but excluding cost of reinforcement as per specifications. Specification No. KBS 4.1,4.6	Cum	98.45	6198.12	Six Thousand One Hundred Ninety Eight Rupees and Twelve Paise Only
4	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting,propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached1 pilasters, buttresses, plinth cilis and string courses cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2	Sqm	1032.40	306.72	Three Hundred and Six Rupees and Seventy Two Paise Only
5	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3	Tonn	14.77	69805.80	Sixty Nine Thousand Eight Hundred Five Rupees and Eighty Paise Only

Signature Of the Contractor
EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer,
Project Division.

6	KSRB 5.2-2 : Providing and constructing granite / trap / basalt size cum 4,037.00 stone masonry in foundation with cement mortar 1:8, stone hammerd dressed in courses not less than 20 cms high, bond stones at 2m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13	Cum	1064.26	3836.16	Three Thousand Eight Hundred Thirty Six Rupees and Sixteen Paisa Only
7	KSRB 4-1.1: Providing and laying in position plain cement concrete of cum mix 1:2:4 with OPC cement @ 240kgs, with 40mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @ 0.459cum 'machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications Specification No. KBS 4.1, 4.2	Cum	110.66	5327.64	Five Thousand Three Hundred Twenty Seven and Sixty Four Paisa Only
8	KSRB 2.3: Filling available excavated earth (excluding rock) in sides cum of foundations upto plinth in layers not exceeding 20 cms. in depth, compacting each deposited layer by ramming after watering with lead upto 50 m. and lift upto 1.5 m. including cost of all labour complete as per specifications. Specification.	Cum	3324.76	239.76	Two Hundred Thirty Nine Rupees and Seventy Six Paisa Only

Signature Of the Contractor
EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer,
Project Division,

6	KSRB 5.2-2 : Providing and constructing granite / trap / basalt size cum 4,037.00 stone masonry in foundation with cement mortar 1:8, stone hammerd dressed in courses not less than 20 cms high, bond stones at 2m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13	Cum	1064.26	3836.16	Three Thousand Eight Hundred Thirty Six Rupees and Sixteen Paisa Only
7	KSRB 4-1.1: Providing and laying in position plain cement concrete of cum mix 1:2:4 with OPC cement @ 240kgs, with 40mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @ 0.459cum 'machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications Specification No. KBS 4.1, 4.2	Cum	110.66	5327.64	Five Thousand Three Hundred Twenty Seven and Sixty Four Paisa Only
8	KSRB 2.3: Filling available excavated earth (excluding rock) in sides cum of foundations upto plinth in layers not exceeding 20 cms. in depth, compacting each deposited layer by ramming after watering with lead upto 50 m. and lift upto 1.5 m. including cost of all labour complete as per specifications. Specification.	Cum	3324.76	239.76	Two Hundred Thirty Nine Rupees and Seventy Six Paisa Only

Signature Of the Contractor
EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer,
Project Division,